



Dump - 400 Tons
 Oz. Gold Oz. Silver
 #176 - 0.29 - 1.50
 535 - 0.09 - 0.32

Dump
 Oz. Gold Oz. Silver
 #177 - 0.29 - 1.50

LOWER TUNNEL

UPPER TUNNEL

Elev. 420

Debris

Elev. 460

Elev. 470

Elev. 495

SHAFT LEVEL
 Elev. 400

SHAFT

168 - 0.8 - 2.07 - 5.75 Floor

170 - 2.7 - 0.006 - Tr. Floor - Ft. side

169 - 3.0 - 0.54 - 4.85 Floor - Hg. side

172 - 0.8 - 0.31 - Tr. Breast

171 - 1.7 - 0.17 Top

173 - 3.9 - 0.025 - 0.10 Top

174 - 1.6 - 0.10 - 0.60 Top

527 - 4.8 - 0.22 - 0.70 Hg. side

526 - 3.8 - 0.34 - 0.70 H.W. Center

523 - 1.9 - 0.82 - 0.20 Tr. Center

524 - 1.4 - 0.01 - 0.24 R.W.

525 - 0.7 - 0.17 - 0.24 R.W.

175 - 0.2 - 0.02 - Tr. Hg. side

166 - 2.1 - 0.60 - 2.83

529 - 1.9 - 0.73 - 3.20

167 - 1.5 - 1.23 - 3.80

- Hornblende Diorite
- Diorite dike
- Aplite dike
- Vein

LOUGHBOROUGH GOLD MINES LTD.
 PLAN OF TUNNELS
 SCALE: 1" = 20'

Survey by Compass and tape.

011931