CHAPELLE PROJECT

METHODOLOGY

030282

Canadian Mine Development Ltd. proposes a two phase underground program on the "B" Zone at the Chapelle Project.

Phase I, an exploration drift, 4' x 7', with arched back, 325 feet long, is designed to verify the ore grade, width, and ground conditions of the drill indicated gold ore zone.

Phase II is dependent on favourable results being obtained in the exploration stage. Costing of the mining phase could be affected by the actual conditions encountered in Phase I.

CHAPELLE PROJECT

METHODOLOGY

PHASE I - UNDERGROUND EXPLORATION PROGRAM

Budgeted cost of this program is \$304,319.

It is proposed that a 4' wide by 7' high arched back drift be driven by jacklegs and slusher for a distance of 325 feet. Targeted ore intersections are contained in holes M86-23, M86-19, and 85-1. The slusher drift would be driven at -2 percent, but this could be modified by the actual collar elevation.

A lump sum provision of \$100,000 is included to cover surface excavation of the 20-30 feet of overburden, broken rock, and for the establishment of the collar.

Attached is the cost estimate and those services supplied by the Contractor and those the responsibility of the Company.

CHAPELLE PROJECT

METHODOLOGY

PHASE II - UNDERGROUND MINING

Best estimate of cost for development and mining 40,000 tons is \$5,477,263 for Phase II.

Phase II is dependent on the results obtained during the underground exploration drift program. The budget mining estimate must be reviewed in light of the ore tenor, widths, continuity, and ground conditions. The cut and fill mining method employing dry fill should allow adequate recovery of the mineable ore. This method has been selected keeping in mind the actual results of the "A" Zone operations.

Access to the drill indicated zone would be by a ramp decline 13' x 10', driven in the footwall, at 18 percent, leaving a 25 foot pillar between the zone and the ramp. A 900 foot long ramp should access the bottom of the zone.

Mining access x-cuts will be driven to the zone. A sill drift, 4' x 6', or to ore width, will be driven to the strike limits. Ground support will be installed on both walls. We feel pattern bolting should prove adequate. A second cut will be excavated before filling. To access the third lift, the ramp x-cut would be slashed or a new x-cut driven.

Additional mining headings could be obtained by mining above the exploration drift.

It is estimated that 100 tons of ore per day will be produced.

CHAPELLE PROJECT

METHODOLOGY

PHASE I - UNDERGROUND EXPLORATION DRIFT

EQUIPMENT LIST

1	slusher, 2 drum, 30 HP, electric
6	jacklegs, stopers
1	generator set, 125 KW
1	compressor, 75 HP, 315 CFM
10	cap lamps, c/w charger
1	fan, 18" diameter
1	fresh water pump, Beam, c/w water heater
1	discharge pump, Flygt, 13 HP
1	lot - first aid and safety gear
1	lot - shop tools, including welder
2	magazines, 1 explosives, 1 cap

CONTRACTOR'S CREW

Mining will continue on 2 shifts.

The site crew will consist of:

Total	8
Miners	4
Mechanics and/or Electricians	2
Cook	1
Project Superintendent	1

CHAPELLE PROJECT

METHODOLOGY

PHASE II - UNDERGROUND MINING

EQUIPMENT LIST

1	iumbo.	electric	hydraulic,	single	boom
_	Juliove	CICCLIC	my was welley	D	

- 1 compressor, electric, 600 CFM
- 2 ST-2 secoptrams
- 1 JDT413 truck
- 1 ventilation fan, 75 HP
- 1 lot cap lamps c/w charger
- 1 welder, 400 AMP
- set oxygen & acetylene torches
- 1 lot shop tools
- 1 lot first aid and safety gear
- 1 lot survey gear
- 4 jacklegs & stopers
- 1 intermediate loader
- 1 fresh water pump
- 1 lot water discharge pumps, Flygt (3)
- 1 Cat D-4 dozer
- 1 radio telephone
- 1 lot grouting gear
- 2 magazines, 1 explosives, 1 cap

CHAPELLE PROJECT

METHODOLOGY

PHASE II - UNDERGROUND MINING

CONTRACTOR'S CREW

Mining will continue on three 8 hour shifts, 7 days per week.

Crew will consist of:

Project Superintendent	1
Shiftbosses	3
Trades Leader	1
Mechanics and/or Electricians	3
Surveyor	1
Cook	1
Miners	6
Total	16

CHAPELLE PROJECT

EXPLORATION AND MINING ESTIMATE

				UNIT		
		UNIT	QTY	PRICE		TOTAL
PHA:	SE I - EXPLORATION					
1.	Mobilization	L.S.		\$ 47,576.00	\$	47,576
2.	Surface Set-up	L.S.		2,415.00		2,415
3.	Trench & Collar	L.S.		100,000.00		100,000
4.	Slusher Drift	ft	325	314.65		102,274
5.	Provision for Ground					
	Support	L.S.		13,000.00		13,000
6.	Air Support during					
	Excavation	L.S.		6,900.00		6,900
7.	Demobilization	L.S.		32,154.00		32,154
PHA:	SE I TOTAL				\$	304,319
PHA	SE II – MINING					
1.	Mobilization	L.S.		\$ 148,115.00	\$	148,115
2.	Collar	L.S.		100,000.00		100,000
3.	Decline	ft	900	418.30		376,470
4.	Crosscuts	ft	250	418.30		104,575
5.	Sill Drift	ft	300	525.62		157,686
6.	Breasting	T	40,000	91.76		3,670,400
7.	Provision for Ground					
	Support	L.S.		400,000.00		400,000
8.	Air Support during Ex	cavation				
	& Crew Transport	L.S.		401,497.00		401,497
9.	Demoblization	L.S.		118,520.00		118,520
РНА	SE II TOTAL				\$	5,477,263
тот	AL PHASE I & PHASE I	((excluding P	hase I Demo	bilization)	<u>-</u>	5,749,428

CHAPELLE PROJECT

MOBILIZATION - PHASE I

Premob Labour

Purchasing, packaging, and preparing equipment for transport.

1 man - 2 weeks

\$13.50/hour x 8 hours x 14 days x 1.34

= \$ 2,026

Fares to Smithers

		9,652	\$ 9,652
2 supervisory trips	$639.00 \times 2 (return) =$	2,556	
4 crew from Sudbury	$709.00 \times 2 (return) =$	5,672	
4 crew from Vancouver	$178.00 \times 2 (return) = $	1,424	

Freight to Smithers - Equipment

30 HP slusher & scraper	4,000 lbs			
250 KW genset	7,000 lbs			
300 CFM compressor	6,000 lbs			
Explosive magazines (2)	6,000 lbs			
Fuel tank	2,000 lbs			
Drills	2,000 lbs			
Fan	1,500 lbs			
Pumps	1,200 lbs			
=	29.700 lbs = 1 load @ \$	5,340	= \$	5,340

24,352

MULTINATIONAL RESOURCES INC.

CHAPELLE PROJECT

MOBILIZATION - PHASE 1

Air Transport - Smithers to Sturdee Strip using Caribou aircraft - 8,000 lbs lift

200 miles @ 7.73/mile x 2 = 3.092.00/trip

EQUIPMENT:

Genset	7,000 lbs
Slusher & scraper	4,000 lbs
Compressor	6,000 lbs
Drills	2,000 lbs
Fan	1,500 lbs
Pumps	1,200 lbs
Pipe	2,000 lbs
Fuel & tanks, 1000 gals	6,000 lbs
Explosives & magazine	6,000 lbs
Misc.	2,000 lbs
	37,700 lbs

=	5 trips + 1 trip with crew + Mob & Demob	= \$	18,552 3,800	
	Loading & unloading labour		22,352	
	Loading & unloading labour	- *	24,352	\$

MOBILIZATION COST	\$ 41,370
FEE 15%	6,206

MOBILIZATION TOTAL \$ 47,576

CHAPELLE PROJECT

MOBILIZTION - PHASE I

|--|

Powder/cap magazine	2 M/S X \$210.00	= \$	420
Fan & heater	$2 \text{ M/S} \times \$210.00$	=	420
Power distribution	$2 \text{ M/S} \times \$210.00$	=	420
Genset installation	$2 \text{ M/S} \times \$210.00$	=	420
Compressor installation	2 M/S x \$210.00	=	420

Water from mill supply - use pump & hose to tank with pump to collar.

	\$ 2,100	\$ 2,100
Fee 15%		315
		\$ 2,415

Collar - Side Hill 45%

Face in bedrock	15 feet
Overburden	20 feet
Total Height	35 feet
Width at base	15 feet
Width at top	85 feet
Length <u>35</u> .45	78 feet

Overburden = 42,000 cu ft @ \$2.08/cu ft = \$ 87,360 SAY \$ 100,000 incl. Fee

CHAPELLE PROJECT

MOBLIZATION - PHASE I

Aircraft Support during Stage I

2 trips/week = 6 trips @ \$1,000

Twin Otter or Beech 19 = \$ 6,000

Fee 15% 900

\$ 6,900 \$ 6,900

Demobilization*

LABOUR for dismantling of installation and transport to the Sturdee strip 2 days x 8 men x \$210.00 = \$ 3,360 AIR TRANSPORT = \$ 4 trips + 1 trip for crew @ \$3,092 15,460 MOB & DEMOB - Caribou aircraft 3,800 FREIGHT from Smithers, 1 load 5,340 27,960 Fee 15% 4,194

32,154

32,154

^{*}Deduct if second stage is mobilized.

CHAPELLE PROJECT

MOBILIZATION - PHASE II

Fares for	addit	ional	crew	+ 8	3 men
-----------	-------	-------	------	-----	-------

ASSUME	4 from Vancouver	\$178.00 x 2	=	\$ 1,424	
	4 from Sudbury	\$709.00 x 2	=	5,672	
				\$ 7,096	\$ 7,096
Freight to	Smithers				
EQ	UIPMENT:				
	2 scooptrams	Brampton to Smithe	rs	\$ 5,340	
	1 truck	Brampton to Smithe	ers	5,340	
	1 One boom jumbo	Brampton to Smithe	rs	5,340	
	75 HP fan)			
	D-4 Cat)		5,340	
	Loader)			
	Jacklegs & stopers)			
	Welders)			
	600 CFM compressor)			

5,340

26,700 \$ 26,700

PIPES & FITTINGS - 1300 ft - 4" & 2" LINE

	Wt/ft	Wt/ft
Pipe	4.30	1.95
Couplings	.20	.08
Valves	.08	.03
Tees	.03	.02
Misc.	.03	.02
Chain, Hangers	.10	.10
	4.74	2.20

Total weight = 6,612 + 2,860 = 9,000 lbs

Misc. pumps

CHAPELLE PROJECT

MOBILIZATION - PHASE II

ELECTRIC CABLE - 1000 ft OF EACH

3 cond. #4/0
3 cond. #6/0
3 cond. #6/0
2 cond. #12/0
3 cond. #2/0
plus reels
3 cond. #2/0
3 cond. #2/0
3 cond. #2/0
5 cond. #2/0
6,000 lbs/1000 ft

GROUND SUPPORT

Rockbolts - 1 per lined ft of development SAY 1000 bolts/6 ft @ 6.9 ea.

= 6,900 lbs

PIPE, CABLE, ROCKBOLTS Vancouver to Smithers = \$

Total Freight \$ 30,200

Air Freight - Smithers to the Sturdee Strip

Hercules aircraft - Mobilization
45,000 lbs capacity - \$8,500/trip

\$ 25,000

3,500

CHAPELLE PROJECT

MOBILIZATION - PHASE II

EQUIPMENT & SUPPLIES	:	
2 scooptrams	50,000 lbs	
1 truck	30,000 lbs	
1 jumbo	20,000 lbs	
1 compressor	9,000 lbs	
Fan	1,500 lbs	
Pipe, cable, bolts	22,000 lbs	
D-4 Cat	30,000 lbs	
Explosives	70,000 lbs	
Drill steel bits &		
repair parts	40,000 lbs	
Total	272,500 lbs = 7 trips	= \$ 59,500
GROUND SUPPORT for I	oading and unloading	= 2,000
	•	
Total Air Freight		\$ 91,500
Total Air Freight TOTAL MOBILIZATION COST FEE 15%		\$ 91,500 \$ 128,796 19,319

CHAPELLE PROJECT

MOBILIZATION - PHASE II

Site	Set-up
------	--------

Site Set-up					
Electrical distribution					
from mill	10 M/S @ \$210.00	=	\$ 2,100		
Compressor installation	4 M/S @ \$210.00	=	840		
Fan & heater installation	2 M/S @ \$210.00	=	420		
Power cables, etc.	3000 ft @ \$10.00	=	30,000		
Power distribution transform	mer	=	20,000		
		•	\$ 53,360		
	Fee 15%		8,004		
		•	\$ 61,364	\$	61,364
Collar Excavation - overburden	as for Phase I		SAY	\$ ir	100,000 cl. Fee
Air Transport Support during Phase	e II				
3 trips/week	65 @ \$1,000	=	\$ 195,000		
	Fee 15%		29,250		
			\$ 224,250	\$	224,250
Crew Changes: 16 men -	$\frac{14,192}{42}$ = \$338	3/day	J		
DUACE II COHEDINE - AEC DAVO	44				
PHASE II SCHEDULE = 456 DAYS		-	\$ 154,128		
Crew Transport	Fee 15%	_	23,119		
CONTRAC	FOR WILL PROVIDE	. – P	HASE 1 , 247	\$	177,247

CHAPELLE PROJECT

CONTRACTOR WILL PROVIDE - PHASE I

- Competent crew and supervision covered with all applicable insurance and permits.
- Mining equipment, as listed in Methodology.
- Parts inventory and maintenance of Contractor's equipment.
- All permanent materials, including:
 - 18" ventilation ducting
 - 1" hose, fresh water line
 - 2" air line
 - 2" water discharge line
 - rockbolts
 - power cable
 - screening
- All fuel, lube, and oil.
- All explosives and accessories.
- Work to good standards and abiding by all rules and regulations of the Province of British Columbia.
- Co-operation with Owner to achieve the most efficient and safe project. Advise the Owner in advance of any important requirements.
- Co-operation, preparation, and assistance in submission of various layouts required to obtain permits.

MULTINATIONAL RESOURCES INC. CHAPELLE PROJECT

CONTRACTOR WILL PROVIDE - PHASE I

- Billings to Owner for work completed, as per Schedule of Payments, no later than 10 days after the end of the work period, the work periods being the 1st to the 15th and the 16th to the end of the month. Schedule of Payments to be agreed between the parties prior to project commencement.
- Agree to co-operate with Owner to reach a mutually satisfactory and just settlement should Contractor's advance be impeded by ground or water control requirements.

CHAPELLE PROJECT

CONTRACTOR WILL PROVIDE - PHASE II

- Competent crew and supervision covered with all applicable insurance and permits.
- Mining equipment, as listed in Methodology.
- Parts inventory and maintenance of Contractor's equipment.
- All permanent materials, including:
 - 42" ventilation ducting
 - 2" fresh water line
 - 6" air line
 - 6" water discharge line
 - rockbolts
 - power cable
 - screening
- All fuel, lube, and oil for Contractor's equipment.
- All explosives and accessories.
- Work to good standards and abiding by all rules and regulations of the Province of British Columbia.
- Survey control.
- Co-operation with Owner to achieve the most efficient and safe project. Advise the Owner in advance of any important requirements.
- Co-operation, preparation, and assistance in submission of various layouts required to obtain permits.

CHAPELLE PROJECT

CONTRACTOR WILL PROVIDE - PHASE II

- Billings to Owner for work completed, as per Schedule of Payments, no later than 10 days after the end of the work period, the work periods being the 1st to the 15th and the 16th to the end of the month. Schedule of Payments to be agreed between the parties prior to project commencement.
- Agree to co-operate with Owner to reach a mutually satisfactory and just settlement should Contractor's advance be impeded by ground or water control requirements.

CHAPELLE PROJECT

OWNER WILL PROVIDE - PHASE I

- author	All access, work, environmental, and other permits required by governmental rities.
of the	Payment to Contractor, as per Schedule of Payments and layouts enclosed, on a monthly basis, the work periods being the 1st to the 15th and the 16th to the end month. All invoices are due and payable 15 days issuance. Schedule of Payments agreed between the parties prior to project commencement.
-	Progress certificates to Contractor after the end of each work period.
- progre	Site representation with sufficient authority to accept or reject Contractor's ess on a daily basis.
- projec	Co-operation with Contractor in order to achieve the most efficient and safe t. Advise Contractor in sufficient advance of any pending changes.
-	Engineering, geological control, and assaying, as required.
-	Water source within 2500 feet of the portal.
-	Water discharge retention ponds, if required.
-	Road access, maintenance, and snow removal throughout contract.
-	Camp and shop - at no cost.
-	One (1) pick-up on site - at no cost.
-	One (1) Toyota station wagon on site - at no cost.

CHAPELLE PROJECT

OWNER WILL PROVIDE - PHASE I

- One (1) hiab crane on site at no cost.
- Agree to co-operate with Contractor to reach a mutually satisfactory and just settlement, should Contractor's advance be impeded by ground or water control requirements.

CHAPELLE PROJECT

OWNER WILL PROVIDE - PHASE II


- All access, work, environmental, and other permits required by governmental authorities.
- Payment to Contractor, as per Schedule of Payments and layouts enclosed, on a twice monthly basis, the work periods being the 1st to the 15th and the 16th to the end of the month. All invoices are due and payable 15 days issuance. Schedule of Payments to be agreed between the parties prior to project commencement.
- Progress certificates to Contractor after the end of each work period.
- Site representation with sufficient authority to accept or reject Contractor's progress on a daily basis.
- Co-operation with Contractor in order to achieve the most efficient and safe project. Advise Contractor in sufficient advance of any pending changes.
- Geological control and assaying, as required.
- Water source within 2500 feet of the portal.
- Discharge retention ponds, if required.
- Road access, maintenance, and snow removal throughout contract.
- Power, 600 KW, from mill generators at no cost.
- Air heating equipment and fuel.
- Camp and shop at no cost.

CHAPELLE PROJECT

OWNER WILL PROVIDE - PHASE II

- On site vehicles: pick-up, Toyota station wgon, and hiab crane at no cost.
- Agree to co-operate with Contractor to reach a mutually satisfactory and just settlement, should Contractor's advance be impeded by ground or water control requirements.

DESCRIPTION 1 2 3 4 3 5 6 7 8 9 10 11 12 13 13 15 16 17 18 19 20 21 12 13 23 23 23 23 23 23 23 23 24 25 25 25 25 25 25 25 25 25 25 25 25 25	DESCRIPTION		· -				,							K S					····							
EXCAVATE TRENCH & COLLAR			2	3	1	5	6	-7_		9	_10_	11_	_12_	13	19_	15	16	17	18	.19	30	21	22 2	2 25	25	4
EXCAVATE TRENCH & COLLAR PRIVE SLUSHER DRIFT PHASE TI MOBILIZATION EXCAVATE TRENCH & COLLAR BRIVE SCLI DRIFT STOPING UPPER & LOWER LEVELS MANPOWER SUPERINFENCENT SUP		-	4=	 	L	 -																	 -			+
PHASE TI NOBILIZATION EXCAVATE YRENCH & COLLAR DRIVE DCLINE DRIVE DCLINE DRIVE DCLINE DRIVE DCLINE DRIVE SULL DRIFT STOPING UPPER & LOWER LEVELS MANDOWER SUPPER NIFTBOOS SUPPER NIFTBOOS LECTRICIAN 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1]																							
PHASE IT MOBILIZATION EXCAVATE TRENCH & COLLAR BRIVE BCLI INE DRIVE SILL DRIFT STOPING UPPER & LOWER LEVELS I 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	EXCAVATE TRENCH & CULLAR		-	-		 	 		ļ	-						-	-							-		4
EXCAVATE TRENCH & COLLAR DRIVE DECLINE DRIVE SILL DRIFT STOPING UPPER & LOWER LEVELS MANIPOWER SUPERINTENDENT 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	DRIVE SLUSHER DRIFT																									1
EXCAVATE TRENCH & COLLAR DRIVE DECLINE DRIVE SILL DRIFT STOPING UPPER & LOWER LEVELS MANIPOWER SUPERINTENDENT 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	DUACE II		-	 	 	ļ	 																		-	- -
MANPOWER STOPING UPPER & LOWER LEVELS MANPOWER SUPERINTENDENT 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		-	 	 	 	 			-																1	1
NRIVE DECLINE	PUR LITA PE VAPATALI NA LA CALLACA																							1	Ţ	Ţ
STOP ING UPPER & LOWER LEVELS MANPOWER STOP ING STOP ING STOP ING	EXCAVATE TRENCH & COLLAR	-		}	ļ	ļ.——			F												<u> </u>				+	+
STOP NG UPPER & LOWER LEVELS STOP 116 STOP 116 SUPER INTEREST 1	DRIVE DECLINE	-	1	1	T	<u>† </u>	<u> </u>							I											1	1
MANPOWER STOPING STOPING STOPING STOPING SUPERINTENDENT SUPE	DRIVE SILL DRIFT			1			ļ	L							-										-}	+
MANPOWER SUPERINTENDENT SHIFTBOOKS MECHANIC 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	STOPING UPPER & LOWER LEVELS	·		-						-				: :										_		+
SUPERINTENDENT 1 1 1 1 1 1 1 1 1				<u> </u>			<u> </u>	<u>L</u>													STOPI	116				
SHIFTBOSS MECHANIC 1 1 1 1 1 1 2 3 3 3 3 3 3 3 3 3 3 3 3 3																										
NECHANIC			1_	<u> </u>	1_1	1_1_	1_1_	1_	1	1_1_	_1	1	1	1	1	1	1_1_		_1_	1	.1_	1	- -	<u> </u>		1
MINER SURVEYOR/ EXPEDITOR	MECHANIC	-	 	1	1	1	1	1	3	- 3-		«	3					3	3	- 3	-3	3	-3	3 3	5	1
SURVEYOR/ EXPEDITOR GOOK I I I I I I I I I I I I I I I I I I I				1	1	1_1_	1		1	1			1	1		1	.1.	1	1	_1			1	1 1		1-
COOK 1 1 1 1 1 1 1 1 1	MINEK SURVEYOR/ EXPEDITOR		 	4	1.4	.4	4	4	1 1							6	1	6			6	6 -	6	6 6		j.
The property The			1	1	i	Ĩ	1	ī	ī	ī	1	ī		î	î.	ī	ī	i			ī		ī	$\mathbf{i} \mid \mathbf{i}$	5	1
The property The		_	Ī	ļ <u>.</u>																				_	ļ	-
The property The			 		ŧ	:																		+	 	+
Table Tabl	TOTAL	ì	1	7	8	8	8	8	16	16	16	16	16	16	16	16	16	16	16	16	16	16	16 1	5 16		1
1	EQUIPMENT		.L			L	L	L		L								L			1				J <u>.</u>	۰.
JDT-413 TRUCK	1-BOOM JUMBO	T	Γ-	Τ_	Ι	Ι		1	1	1	1	1	1.	1	1	1	1	1	1	1.	1.	1.	1	11_1	<u></u>	Γ
COMPRESSOR I I I I I I I I I I I I I I I I I I I		- 1							_ 2	2	2	. 2	2	2	2	. 2	2	.2.	2	. 2	.2_	2_	2	22	<u>.</u> .	-
COMPRESSOR I I I I I I I I I I I I I I I I I I I	SLUSHER/ SCRAPER			1.	₁	1	1		ī	- i	<u>i</u>	1	1	1	1	ì	1	1-	1	- 1	1	1 -1	-1 ··	1 1	-	-
D-4 DOZER JACKLEG / STOPER LOT LOT LOT LOT PUIPS U/G FANS & HEATER LOT LOT LOT LOT SMALL TOOLS				·										. 1]					-
JACKLEG / STOPER LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT SMALL TOOLS LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT	COMPRESSOR	_		1.		1	1	1	_1	1.	1	1	1	1	.1	1	1.	1	1	. 1	1	.1 .	.1 .	1 _ 1	>	-
PUIPS U/G FANS & HEATER LOT		1				•	t .				- 1						.	1							-	l
SMALL TOOLS LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT LOT	PUNPS		1	LOT	LOI	LOT	 																	-	-	
SPACE 100LS		-		LOT	LOT	LOT	.			-::	٠	- 1					-				二					
	SPALL IDOUS		ł	LOT	LÛT	L01	7					_													-	-
												SCAL	e,		DATE	· ·	`	ME	TIMATI	ONAL RE	SOURCES	INC.	Canadian	More De	relopmen	
SCALE LOATE! INSTITUTE OF COUNTS IN CARAGON MORE Development	·											DES	ONED K	MCG.] · ·	LHAPPEL	1 E 60L	B PROPE		Massing DWG Mc	• 0		Ç,
BCALE DATE DESCRIBE K.W. DRAWN S. MCG. CHECKED h.R. CHECKED h.R. APPROVID IT DESCRIBED MAN Development Manifestal h.R. WORK SCHEDULE 87 - 01 - 001												CHE	MED /	12.7	I I]]	T .	1	WORK	ec ni	CUIR 6			01 -		ľ



> DRILL 12 HOLES BLAST 12 HOLES

cour. 1:22	1 2175	-
DESIGNED: 5. MG	DATE	4
DRAWN: 5, MCG,	-AN/87	No.
CHECKED: KRW	"	
APPROVED: IT FILL	11	





1	MULTINATIONAL RESOURCES INC. CHAPPELLE GOLD PROPERTY
	1.22 × Z.B.
-	ROEDSTING

C. CANADIAN MINE DEVELOPMENT LTD. BRAMPTON, ONT. CANADA

BREASTING 87 - 01 - 009

Transt





DESIGNED: 7. J.

DRAWN: 5. ME CO JUNE / 86

CHECKED: 7 05/06/86

APPROVED: 7 106/86



MULTINATIONAL RESOURCES INC.
CHAPPELLE GOLD PROPERTY

3. OM = 4.0m RAMP

TYP, X-SECTION


MULTINATIONAL RESOURCES INC. CAMADIAN MINE DEVELOPMENT LTD.
CHAPPELLE GOLD PROPERTY

BRAMPTOR, ONE

CAMADIA

DING. Mo.

87 - 01 - 007



CAP No.	AMOUNT
0	1
1	1
2	1
3	2
4	2
5	4
6	4
7	4
8	3
9	7
10	3
11	7
12	3
TOTAL	$\frac{3}{42}$
, _	2007 - 2014 to


DRILL 45 HOLES BLAST 42 HOLES

SCALE: /:20
DESIGNED: DRAWN: 5, M = 6, JUNE | 86 CHECKED: T), 05/06/86



MULTINATIONAL RESOURCES INC. CANADIAN MORE DEVELOPMENT LTD.

3ms 4m RAMP . 87 - 01 - 006



CAP No.	AMOUNT
0	1
1	
Z	1 11
3	2
4	2.
5	4
6	4
7	4
B	3
9	7
10	3
11	7
12	3 42
TOTAL	42

DRILL 93 HOLES BLAST 42 HOLES


SCALE: /: 20	DATE	
DESIGNED:		6
RAWN: 5, MCG.	4/86	-
CHECKED: T)	05/06/1	
======================================		




MUL	TIN	ATIO PELL	NAL E 6	RES	PRO	CES	INC.

CANADIAN MINE DEVELOPMENT LTD.
BRAMPTON, ONE CANADA
DWG, No. REV.

SMY AM PORTAL 87 - 01 - 005





1 2 3 4 5 6	AMOUNT 1 1 1 2 4 4
7	4
8	3
9	3
TOTAL	25

DRILL 28 HOLES
BLAST 25 HOLES

SCALE: //10	DATE
DESIGNED: 6.V.	
DRAWN: 5, MCG.	184.187
CHECKED: KREW	14
APPROVED: KREE	IN



ULTINATIONAL RESOURCES INC. CHAPPELLE GOLD PROPERTY	CANADIAN MINE DEVELOPME	ENT LTD.
1.11 - 2.13 - T	DWG. No.	REV.

