

AVONDALE RESOURCES INC. (AVD-V)

HOLE NO.	INTERVAL FEET	LENGTH FEET	GOLD OZ/T	SILVER OZ/TON	COPPER %
AVD90-4	39.4 - 59.1	19.7	0.012	0.05	0.12
AVD90-5	78.7 - 167.3	88.6	.052	.58	1.10
Incl.	128.0 - 137.8	9.8	.130	3.91	8.55
AVD90-6	19.7 - 26.2	6.6	.107	.06	.01
	36.1 - 39.4	3.3	.106	.13	.05
AVD90-7	104.2 - 229.71	125.5	.051	.20	.36
Incl.	141.1 - 160.8	19.7	.090	.50	1.29
AVD90-10	111.6 - 196.9	85.3	.072	.23	.46
	111.6 - 131.2	19.7	.096	.68	1.37

FORREST KERR DRILL RESULTS - John Ivany, president, reports Avondale Resources has discovered a large gold/silver/copper mineralized system on its Forrest Kerr project located about 65 miles northwest of Stewart, B.C. The discovery was made during the initial 15-hole drilling program. Three other new gold showings were also discovered during surface work. The table above shows assays from drilling on the Creek, Triple Creek and Canyon showings on the south side of Gossan Creek and the Forrest zone.

Holes AVD90-4, 5, 6, 7, and 10 were all drilled on the Creek showing, a zone containing chalcopryite, pyrite and arsenopyrite. This zone has been traced over a strike length of 200 feet by drilling. Hole AVD90-4 intersected the zone about 75 feet above AVD90-5, and AVD90-6 intersected the zone about 140 feet above AVD90-7. Assays from AVD90-6 and 7 indicate the zone is widening and gaining in strength at depth. Holes AVD90-5 and 7 bottomed in anomalous gold mineralization.

Holes AVD90-1, 2 and 3 were all drilled on the Triple Creek showing, lying some 350 feet west of the Creek showing. Hole AVD90-8 was drilled on the Canyon Shear with weakly anomalous results. Hole AVD90-9 was a stratigraphic test of the quartz stockwork system which comprises the Forrest zone, which features numerous quartz veins and stockworks over an area of about 1,600 by 1,600 feet. Induced polarization surveys over the Forrest zone will be carried out to locate other drill targets.

Elsewhere on the property, the 50 Zone is the site of backhoe trenching as well as VLF-EM and IP surveys. Work on the Alpine zone has been delayed by lingering snow cover. Avondale will start a second phase of drilling on the project this month following completion of the trenching, mapping and geophysical surveys.

NO.152(1990)
AUGUST 8, 1990

George Cross

Reliable

WESTERN CANADIA

Avondale also reports the collaring of the portal site for the \$2,500,000 underground exploration program for the AK zone on the Inel project, located 18 miles west the the Eskay Creek 21 Zone, where the company has an option to earn a 50% interest from GULF INTERNATIONAL MINERALS LTD. (GIM-V). The program entails about 1,500 feet of adit and footwall drifting to establish drilling sites. A crew of 16 is working continuously with 11,000 feet of drilling expected to start within six weeks. (SEE GCNL No.131, 9Ju190, P.3 FOR PREVIOUS DETAILS)

104B General
p. 2 of 2