

NO.187(1990)
SEPTEMBER 27, 1990

George Cross

Reliable

WESTERN CANADIA

AVONDALE RESOURCES INC. (AVD-V)
GULF INTERNATIONAL MINERALS LTD. (GIM-V)

HOLE NO.	INTERVAL FEET	DIP DEG.	LENGTH FEET	GOLD OZ/T	SILVER OZ/TON	ZINC %
U-170	259.0 - 270.0	+36.5	11.0	0.045	0.11	0.31
U-171	227.5 - 251.8	+26.0	24.3	1.197	1.39	.87
Incl.	231.0 - 247.0		16.0	1.574	1.72	.97
U-172	162.7 - 208.8	+16.5	46.1	.130	.11	.05
Incl.	162.7 - 166.0		3.3	.918	.56	.21
U-174	135.0 - 140.0	+28.0	5.0	.269	.84	.48
And	296.0 - 324.0		28.0	.158	.19	.13

INEL DRILL RESULTS - William Campbell, secretary,

reports Avondale Resources Inc. has received assays from Gulf International Minerals Ltd. for the initial five holes of the underground drilling program on the Inel project in the Iskut River area about six km east of Johnny Mtn., 100km NW of Stewart, B.C. Avondale, the operator, can earn a 50% interest from Gulf by paying \$150,000, issuing 500,000 shares and spending \$10,000,000 on exploration. SEE ASSAYS ABOVE.

Drilling is testing the AK zone where surface drilling in 1989 indicated gold and base metal mineralization occurs over true widths of 6-18 feet in an intrusive breccia at the footwall contact of a syenite intrusive.

Holes U-170 to 173 are a fan of holes at Azimuth 060 degrees from the first underground drill station; hole 174 was drilled from the same station to start a second fan of holes at Azimuth 080 degrees. The intercept reported for the intrusive breccia in hole U-174 is not complete; more to come from 324.0-341.4 feet. Hole U-173, at a dip of 19.5 degrees, was abandoned at 138 feet before reaching the target.

The underground drilling began in an area of the AK zone where drilling intercepts in 1989 included 24.0 feet of 0.628 oz.gold/ton, 13.1 feet of 1.508 oz.gold/ton and 20 feet of 0.422 oz.gold/ton. The underground exploration program entails about 1,500 feet of adit and footwall drifting to establish drilling stations for about 12,000 feet of drilling to test the continuity of the AK mineralization over a minimum 1,000 feet of strike length. Budget for the underground work is a minimum \$2,500,000. (SEE GCNL No.179, 17Sep90, P.3 FOR PREVIOUS INFORMATION)

104B 113