

1710 - 609 GRANVILLE ST
PO BOX 10363
VANCOUVER BC
CANADA V7Y 1G5
(604) 683-7265 FAX 683-5306
BBS 683-7206

George Cross News Letter

"Reliable Reporting"

WESTERN CANADIAN INVESTMENTS

COPYRIGHT
ALL REPRODUCTION
RIGHT RESERVED
PUBLISHED DAILY
SUBSCRIPTION RATE
\$350.00 PER YEAR

NO. 204 (1995)
OCTOBER 24, 1995

NO. 204 (1995)
OCTOBER 24, 1995

GETCHELL RESOURCES INC.

[GHS-V] 3,820,946 SHS.

TECK CORP.

[TEK.B-V, T, M] 86,633,589 SHS.

RAINBOW PROJECT DRILLING UPDATE - James T. Gillis,

president,


Getchell Resources Inc. (30%), and Teck Corp. (70% and operator), and have completed the second phase of drilling on the Rainbow property, located about 10 km southwest of Kamloops, B.C. SEE CLAIM MAP OVERLEAF P.1. The first phase drill program, completed earlier in 1995, confirmed a copper-gold mineralization zone outlined by previous operators (Number 2 Zone). Results of the first phase of drilling have been previously released.

The second phase of drilling, totalling about 3,600 metres in 14 drill holes, expanded the area of previously known mineralization.


The copper-gold mineralization zone extends for roughly 650 metres in plan and has been intersected in drilling to a depth of 200 metres. Results to date indicate mineralization is now related to a breccia zone within an extensive hydrothermal system. Previous operators using a different model, has not adequately tested this style of deposit. Mineralization may extend beyond the area of current drilling. Teck and Getchell have now completed about 6,000 metres of drilling in 27 holes.

Assays for holes 95-14 to 94-27 are listed overleaf P.3. Location of these holes are plotted on the map OVERLEAF P.2. Complete results for the 1995 program are being evaluated by Teck, Getchell and Afton Operating Company to determine the extent of the next phase of exploration. (SEE GCNL NO.176, 13Sept95, P.3 FOR PREVIOUS RAINBOW PROJECT INFORMATION)

92 I N E 28
P 10 F 4



92LINE 28 p. 3 of 4



TECK EXPLORATION LTD.
Getchell Resources Inc.

1995 DRILLING on the RAINBOW PROPERTY

GETCHELL RESOURCES INC.
TECK CORPORATION

Rainbow Project
Kamloops Area, B.C.

92LINE 28
P. 4 of 4

RAINBOW PHASE II-DDH RESULTS

All holes are drilled @ -45 degrees.

N.B. R-23,24 are drilled @ 270 degrees, all other holes are drilled @ 180 degree azimuth.

HOLE #	E-W	N-S	From (m's)	To (m's)	Interval (m's)	Cu %	Ag g/T	Mo ppm
R-95-14	1+25 E	0+55 S				NSV	NSV	NSV
R-95-15	1+25 E	0+75 N	22.5	40.5	18.0	0.12	0.10	NSV
			118.0	246.0	128.0	0.17	0.03	
		incl.	118.0	166.0	48.0	0.20	0.03	
R-95-16	0+75 E	0+75 N	144.5	282.5	138.0	0.47	0.15	
		incl.	186.5	243.5	93.0	0.58	0.16	
		incl.	225.5	243.5	18.0	0.98	0.16	
R-95-17	0+25 E	2+05 N	35.6	65.6	30.0	0.23	0.10	
R-95-18	0+25 E	0+90 N	180.5	336.5	156.0	0.47	0.11	
		incl.	222.5	303.5	81.0	0.72	0.17	411
		incl.	231.5	270.5	39.0	0.88	0.25	
R-95-19	0+25 W	0+70 N	151.0	294.7	143.7	0.27	0.10	
		incl.	196.0	238.0	42.0	0.44	0.16	
R-95-20	0+75 W	1+00 N	141.5	297.5	156.0	0.22		
		incl.	225.5	264.5	39.0	0.52	0.10	
R-95-21	0+75 W	0+50 N	19.4	37.4	18.0	0.11	0.03	
			55.0	76.0	21.0	0.14		
R-95-22	2+75 E	0+00 N	234.0	300.0	66.0	0.88	0.23	
		incl.	240.0	291.0	51.0	1.03	0.26	
		incl.	273.0	291.0	18.0	1.44	0.38	
R-95-23*	2+00 E	0+50 S	66.0	279.0	213.0	0.48	0.10	
		incl.	135.0	228.0	93.0	0.89	0.17	
		incl.	165.0	207.0	42.0	1.05	0.24	
R-95-24*	1+50 E	1+00 S	48.6	306.9	258.3	0.72	0.15	
		incl.	171.6	267.6	96.0	1.40	0.24	448
R-95-25	3+75 E	0+70 S	270.0	300.0	30.0	0.42	0.06	
R-95-26	2+80 E	1+05 S				NSV	NSV	
R-95-27	2+25 E	1+25 S	81.1	153.1	72.0	0.36	0.16	
		incl.	114.1	144.1	30.0	0.68	0.35	