

1710 - 609 GRANVILLE ST
 PO BOX 10363
 VANCOUVER BC
 CANADA V7Y 1G5
 (604) 683-7265 FAX 683-5306

George Cross News Letter

"Reliable Reporting"

WESTERN CANADIAN INVESTMENTS

COPYRIGHT
 ALL REPRODUCTION
 RIGHT RESERVED
 PUBLISHED DAILY
 SUBSCRIPTION RATE
 \$350.00 + GST

NO. 195 (1996)
 OCTOBER 8, 1996

NO. 195 (1996)
 OCTOBER 8, 1996

CAMNOR RESOURCES LTD.
 [CMB-V] 7,978,924 SHS.
GOLD GIANT MINERALS INC.
 [GMR-V] 8,233,156 SHS.

WILLOUGHBY DRILLING UPDATE - D. Bruce McLeod, president of Camnor Resources Ltd., and 50/50 joint venture partner Gold Giant Minerals Inc. report all gold assays for the second stage of underground drilling recently completed at the Willoughby property have been received. The property is located 26 km east of Stewart, BC immediately adjacent to Royal Oak Mines Ltd.'s Red Mountain Mine property where an evaluation to increase the previously reported 1,000,000 ounce gold reserve is presently being conducted.

The purpose of this stage of underground drilling at the Willoughby property was to systematically test the North Zone along strike and to complete limited wildcat drill testing of structures within reach of the North Zone adit, known to host gold/silver mineralization. Prior to drilling, the North Zone adit was extended southwards 40 metres. In this stage, 10 holes totalling 687.5 metres were drilled. A total of seven holes were designed to test the North Zone. Four holes (96-21 to 96-24) were drilled from station 3040N with the remaining holes (96-25 to 96-27) drilled from station 3020N. All seven holes intersected the North Zone. Combined with earlier drilling, the North Zone has been shown to have a minimum strike length of 100 metres, a minimum dip length of 75 metres with widths being variable to 8 metres. Grades are highly variable.

Following is a summary of the results of the recently completed program. Silver assays are pending.

HOLE NO.	INTERVAL METRES	LENGTH METRES	GOLD OZ/T
96-21	41.8-43.0	1.2	0.045
96-22	STRUCTURE INTERSECTED, CHECK SAMPLING BEING CONDUCTED		
96-23	11.8-12.3	.5	.102*
96-24	12.4-15.6	1.2	.198
	27.4-30.1	2.7	.086
	39.9-40.9	1.0	.109*
96-25	00.0-01.0	1.0	.068
	43.7-44.8	1.1	.042
96-26	16.7-17.9	1.2	.055
96-27	15.8-17.8	2.0	.112
	67.9-69.0	1.1	.063

*HANGING SAMPLE

Holes 96-28 to 96-30 were wildcat holes drilled from station 3020N, these holes intersect weakly anomalous gold bearing zones.

The following is a summary of results:

HOLE NO.	INTERVAL METRES	LENGTH METRES	GOLD OZ/T
96-28	9.8-10.8	1.0	0.051
	56.2-57.2	1.0	.071
96-29	75.4-76.5	1.1	.045
96-30	96.4-100.7	4.3	.038
	109.0-110.3	1.3	.038

At the completion of the underground drill program, the drill

was demobilized. Presently, surface drilling is ongoing to test the various targets on the property outside of the North Zone. The original budget called for 1,750 metres of surface drilling. To date, in excess of 3,050 metres have been drilled and is expected to be completed within the original budget of \$1,200,000. (SEE GCNLT NO 184, 23Sep96, P.3 FOR PREVIOUS WILLOUGHBY PROJECT INFORMATION)

103P 6