Approximate augite diorite contact (surface)
El. 3055'
El. 3050'
El. 3040
El. 3028
El. 30050
El. 2985
El. 2998
El. 2993
Trail to Pioneer Mine & Bridge River
Trail to P.G.E. Railway
"PEP" adit
El. 2918'
Projected development in "PEP" adit, el. 2918'
Gold Creek
Dump
El. 3184' contour
"49-ER" ADIT
El. 3187'
Creek from "Mac" adit & penstock
Greenstone contact at El. 2918' ("Pep" level)
Water pipe-line
Compressor house
El. 3215'
El. 3329.6
Trail
NORTH Astronomic
26°
Magnetic
No. 1 Fault centre at El. 2918' ("Pep" adit level)
41°
East Segment at El. 2918' ("PEP" ADIT level)
65°
No. 2 Fault at El. 2918' ("Pep" adit level)
38°
"MAC" ADIT
El. 3320'
Tak fault
59°
63
Timbered
No. 3 LEVEL
El. 3400.
No. 2 LEVEL
El. 3550'.
No. 1 Fault centre at "49-er" level
44°
40-40
50
68
East Segment "49-er" level.
65°
RAISE COMPLETED JUNE 1961 BY CASSIAR COPPERFIELDS LTD (APPROX POSITION). SEE ALSO PEP LEVEL PLANS.
53°
Pioneer Greenstone at "49-er" adit level.
No. 1 LEVEL
El. 3650'
(Caved)
Caved on No. 2
Glory-hole to No. 1 level.
Caved
No. 1 Fault on No. 3 level
165' to face
37°-50°
No. 1 Fault on No. 3 Level
No. 2 Fault on "49ER" level.
38°
No. 1 Fault on No. 2 Level
Vein
East Segment No. 3 level
38° on No. 3 Level
No. 2 Fault
No. 1 Fault centre at el. 3615'
40°
East Segment at el. 3615'
El. 3615

GOLDEN CONTACT MINES LTD. (N.P.L.)

Main Workings

Scale
0 40 80 120 160 200 Feet

With report by: Joseph T. Mandy, M.E., Ph.D.
Consulting Mining Engineer,
Vancouver, B.C. November 12, 1949.

60642

60642