

ADRIAN RESOURCES LTD. (ADL-V)

SKYLINE GOLD CORP. (SKX-V)

HOLE NO.	INTERVAL FEET	LENGTH FEET	GOLD OZ/T	SILVER OZ/TON	LEAD %	ZINC %	COPPER %
SC91-01	6.6-25.1	18.5	0.063	0.61	0.89	1.93	0.08
Incl.	6.6-13.2	6.6	.064	1.01	2.09	3.74	.09
	124.6-139.0	14.4	.105	.62	.39	2.30	.06
SC91-02	16.4-23.0	6.6	.106	.55	.15	4.66	.11
	25.3-49.2	23.9	.137	.65	.55	3.72	.15
Incl.	25.3-32.8	7.5	.172	.95	1.00	5.91	.12
	108.9-121.0	12.1	.080	.42	.36	2.26	.12
Incl.	111.5-118.1	6.6	.116	.46	.50	2.49	.15
SC91-03	56.1-75.5	19.4	.107	.52	.71	2.77	.18
Incl.	56.1-62.3	6.2	.145	.71	.52	4.63	.24
SC91-04	63.0-111.5	48.5	.133	.94	.17	5.74	.13
Incl.	82.0-105.0	23.0	.164	1.23	.26	7.28	.15

SKY CREEK SMC ZONE ASSAYS RECEIVED- Murray Pezim, chairman, Adrian Resources Ltd., reports assays have been received for four drill holes completed on the SMC zone of the Sky Creek project located immediately south of the SNIP mine and adjoining the Skyline Johnny Mountain property in the Iskut River area of northwest B.C. Adrian can earn a 51% interest by spending \$1,600,000 on exploration, issuing 200,000 shares and granting Skyline Gold Corp. options to buy 150,000 shares of Adrian at prices varying from \$2.75 to \$4.75 per share over three years.

A gold equivalent calculation based on current metal prices for drill hole SC91-04 indicates a value of 0.304 oz./ton gold equivalent over the 48.5-foot interval and 0.381 oz. ton gold equivalent over the 23-foot section reported in the table above. Results from holes SC91-01 to 04 compare favourably with values obtained from surface channel sampling from trench No.2, which returned 0.119 oz.gold/ton, 1.14 oz.silver/ton, 2.06% lead, 5.15% zinc and 0.23% copper over 54.1 feet.

Since the discovery of the SMC zone adjacent to the road connecting the SNIP and Johnny Mountain mines in June, similar mineralization has been observed over a minimum 400-meter strike and a coincident VLF-EM conductor has been defined for a minimum 1,200-meter strike length. The stratigraphic package hosting the SMC mineralization displays a number of sub-parallel VLF-EM conductors over similar strike extensions.

Results are pending for an additional seven holes drilled on the SMC zone, two holes completed on the Tillerman showing and single-hole tests of the Upper Road showing and Skyline's original Road showing. (SEE GCNL No.177, 13Sep91, P.1 FOR PREVIOUS INFORMATION)

104B 264